



CORPUS PUBLISHERS

Current Trends in Engineering Science (CTES)

ISSN: 2833-356X

Volume 3 Issue 6, 2023

Article Information

Received date : October 25, 2023

Published date: November 10, 2023

*Corresponding author

Zhibin Li, School of Civil Engineering
and Architecture, Guangzhou City
Construction College, China

DOI: 10.54026/CTES/1048

Keywords

Prefabricated buildings; Structural
system selection; Value engineering; Life
cycle cost; Functional coefficient

Distributed under Creative Commons
CC-BY 4.0

Research article

A Value Engineering Approach for Structural System Selection of Prefabricated Buildings

Ce Gao^{1,2}, Zhibin Li¹ and Yiming Xu³

¹School of Civil Engineering and Architecture, Guangzhou City Construction College, China

²School of Civil Engineering, Guangzhou University, China

³Sinohydro Bureau12 Co., LTD., China

Abstract

The development and implementation of prefabricated buildings has been accelerating rapidly in recent years due to the ongoing revolution in the construction industry. Among different stages and aspects in completing a prefabricated building project, the selection of the prefabricated structural system is a crucial step because it has direct influence on both the cost and usage of the building. This paper proposed a structural system selection model for five commonly used prefabricated buildings structures based on value engineering's value coefficient analysis ranking which took both life cycle cost coefficient and functional coefficient into consideration. The proposed model aims at providing an innovative approach assisting early decision making on the selection of structural systems for project stakeholders. The case study provided in this paper demonstrated the feasibility and effectiveness of the proposed model. With proper implementation, the proposed approach can also promote the development of prefabricated buildings due to their cost and value advantages.

Introduction

The urbanization development is still at high speed globally, as a relatively new and more sustainable building type, the prefabricated building (PCB) has become increasingly popular in the construction industry. For PCBs, there are various types of structural systems and each has different cost and functional characteristics. Selecting appropriate structural system of PCBs that will satisfy the owner's and end user's needs is one of the most crucial decisions of the project, because it determines or directly affects the basic structure, cost, construction and the actual usage of the building. Thus, to further promote the usage and better development of PCBs, this paper developed a value engineering based structural system selection model that can consider both their costs and functional factors from life-cycle perspective for PCBs.

A comprehensive literature review was conducted on literatures that are related to PCBs and their structural system selections in the globe. This literature are categorized into four categories, including fire resistance of prefabricated components [1], life cycle design of prefabricated buildings [2], emission of greenhouse gases [3] and life cycle energy consumption of prefabricated buildings [4]. Jin analyzed studies conducted in the past decade that focused on the development of prefabricated buildings overseas and provided the conclusion that the main focuses are construction performance of prefabricated buildings [5,6] application of prefabricated building management [7,8] and analysis of the factors influencing the development of prefabricated buildings [9,10]. Other studies are limited to economic benefit evaluation [11,12] information management based on BIM [13,14] and seismic behavior of prefabricated components [15]. Also, most of the related research used concrete structures as the research objects [16,17]. Some other studies were about the application of prefabricated buildings structural systems [18,19], design of prefabricated buildings structural systems [20,21] and economic performance of prefabricated buildings [22].

Past research has indeed enriched the research of prefabricated buildings, but few studies were conducted on the selection of structural systems of prefabricated buildings, especially took both cost and functional factors into consideration. Considering its importance, this paper proposed a structural system selection model for five commonly used prefabricated buildings structures based on value engineering's value coefficient analysis ranking which took both life cycle cost coefficient and functional coefficient into consideration. A case study is also provided in this paper to demonstrated the feasibility and effectiveness of the proposed model.

Structural System Analysis of Prefabricated Buildings

Compared to traditional construction methods and building types, prefabricated buildings transferred a lot of on-site works to factories for prefabrication. For example, floors, wallboards, stairs and balconies can all be prefabricated and transported to the construction site. Then, reliable connection members are used to install the components [23]. Mainly used prefabricated building structures include concrete structure, steel structure, wood structure and mixed structure. In this section, the characteristics of five commonly used prefabricated structures are compared [24-29] and is shown in Table 1.

**Table 1:** Comparison of structural characteristics of five fabricated concrete structural systems.

	Fabricated frame Structural System	Fabricated frame Cast-in-Situ Shear Wall Structural System	Prefabricated Shear Wall Structural System	Double Side Composite Plate Shear Wall Structural System	Externally Hung and Internally Cast PCF Shear Wall
Prefabricated components	Columns, composite beams, exterior walls, composite floors, etc	Frame columns, beams, shear walls, peripheral wall panels, internal partitions, etc	Shear walls, composite floors, stairs, interior partitions, etc	Shear wall, composite floor, stair, balcony, interior partition, etc	Exterior wall, laminated floor, balcony, stair, laminated plate, etc
Seismic performance	7 degrees	6-8 degrees	6-8 degrees	7 degrees	6-8 degrees
Construction difficulty	higher	higher	higher	Lower	Lower
Construction efficiency	Lower	Lower	Lower	higher	higher
Connection mode	Dry connection+wet connection	Dry connection+wet connection	Effective cast-in-place	Joint bar connection	Traditional cast-in-place
Assembly rate	15%-65%	40%-85%	30%-80%	Up to 40%	15%-20%
Prefabrication rate	20%-80%	45%-90%	40%-85%	Up to 50%	15%-35%
Construction cost	higher	higher	higher	Lower	Lower
Applicable height	Below 50m	High rise, super high rise	High rise	High rise, super high rise	High rise, super high rise
Applicable buildings	Apartments, hotels, schools, industrial buildings, etc	High rise office buildings, high-rise hotels, apartments, etc	Commercial housing, affordable housing, etc	Commercial housing, affordable housing, etc	Commercial housing, security housing, office buildings, etc
System characteristics	High degree of industrialization, good freedom of internal space, and exposed indoor beams and columns	Small quantities and regular shape at node connection are conducive to energy conservation	High degree of industrialization, complete room space, no exposed beams and columns, general spatial flexibility	High industrialization, fast construction speed, simple connection, light component weight, low precision requirements, etc	The vertical load-bearing structure is cast-in-situ, and the external wall hanging plate does not participate in the force, and it is often used in conjunction with the large steel formwork construction

Structural system Selection Model of Prefabricated Buildings

Proper application of prefabricated buildings requires simplicity of construction operation, feasibility of production as well as basic architectural aesthetics. Thus, for different projects, the design concept and structural system selection should take site conditions, owner's needs, safety, cost and functions into consideration to ensure successful application of prefabricated building technologies on the project.

Methodology

Prefabricated buildings can also be considered as special merchandise that requires long time and complicated resource support to produce. Thus, cost performance, especially life-cycle cost performance needs to be considered. In ordinary construction project management, the traditional cost reduction process often lacks consideration of the "whole picture" from design to construction and to the actual usage of the building. In contrast, value engineering cost reduction process comprehensively considers cost, function, value and users' benefits. Thus, using value engineering to evaluate the structure selection of prefabricated buildings has

significant advantages over traditional approaches.

Although prefabricated buildings often take longer time and has larger demand in the design and cost estimation phase, they have significant time and cost savings in the construction phase [30]. Also, life-cycle cost analysis should be implemented to take complicated cost factors into consideration and to provide a more comprehensive perspective for the project. Thus, in this study life-cycle cost was used for the buildings cost coefficient analysis.

Then, for value engineering, commonly used value coefficient calculation methods include direct scoring method, forced scoring method, multiple ratio method, analytic hierarchy method, entropy weight method, multi-objective maximum distance method and functional system scoring method [31]. Among which, the force scoring method, especially its 0 to 4 scoring method is best suitable for this study because it fits the fact that prefabricated buildings have relatively less functional indicators and they are not significantly dependent to each other. Thus, the 0 to 4 scoring method was used for the building's functional coefficient analysis.

Model development for structural system selection of prefabricated buildings

Theoretical basis of value engineering

Value engineering was firstly developed by design engineer Lawrence D. Miles of General Electric in the United States in 1947 when he was studying raw material substitutes. In 1954, this method was implemented by the United States Navy and was named value engineering. The first-time value engineering was introduced in China was in 1979, with decades of application, it is now widely used in machinery, chemical, construction, metallurgy and other industries.

In value engineering, value means the measurement of the something's benefits. Higher value means that the product, decision, measure or object has more benefits or functions over its cost and is more efficient. Function is the performance or use, in essence, is the use value of the product. In this paper, it is the goal achieved through different structural systems. At last, the cost means the total expenditure of the products in the whole life cycle. When calculating the full life cycle of a building, there is also the cost of demolition and recovery, that is, the full life cycle cost C = production cost C_1 + use cost C_2 + demolition and recovery cost C_3 . Thus, the value can be calculated as the ratio between its functions and cost, as shown in equation 3-1:

$$V = F \div C$$

Where V is the value, F is the function and C is the cost. Value V : refers to the ratio of the function of an object to its total cost. The value studied in this paper represents the economic benefits of the product.

Life cycle cost analysis of prefabricated buildings

The life cycle of prefabricated buildings refers to the whole process of prefabricated buildings from conception to decision-making, from design to construction, from use to maintenance, and finally to scrapping. The life cycle cost is any cost happens within the whole life cycle, this includes recurring or one-time expenses, as well as indirect or direct expenses [32]. The LCC can be divided into different categories as shown in Figure 1.




Figure 1: Life cycle cost of prefabricated buildings

The calculation formula of life cycle cost of prefabricated buildings based on time value is:

$$C = C_1 + C_2 r_1 + C_3 r_2 \tag{3-2}$$

$$C_1 = C_{11} + C_{12} + C_{13} + C_{14} \tag{3-3}$$

$$C_2 = C_{21} + C_{22} + C_{23} + C_{24} \tag{3-4}$$

$$C_3 = C_{31} - C_{32} \tag{3-5}$$

Where C is the total life cycle cost of prefabricated buildings; r_1 and r_2 are cash conversion coefficients

Selection and analysis of functional indicators of prefabricated buildings

When analyzing and selecting the functional indicators of the prefabricated building structural system, after reviewing existing literatures, three functional dimensions, include construction feasibility, environmental effect and brand effect are selected [33,34]. Figure 2 shows the prefabricated building functional indicator system used in this study.




Figure 2: Functional index system of prefabricated buildings.

By analyzing the functional indicators of the prefabricated buildings in Figure 2, the indicators are compared in pairs using the 0 to 4 scoring method based on the scoring principles shown in Table 2.

Table 2: Scoring principle of 0-4 scoring method.

Meaning	Score of F_m	Score of F_n
Compared with F_n , F_m is less important than F_n	0	4
Compared with F_n , F_m is less important than F_n	1	3
F_m is as important as F_n as F_m	2	2
F_m is more important than F_n	3	1
F_m is more important than F_n	4	0

The 0-4 scoring rule in Table 2 is used to determine the weight of prefabricated building function indicators. The results after expert scoring are shown in Table 3.

Table 3: Weight coefficient of function index of prefabricated building.

Function	f11	f12	f13	f14	f21	f22	f23	f24	f31	f32	Score	Weight
f ₁₁	×	2	1	3	3	3	2	2	3	2	21	0.117
f ₁₂	2	×	2	4	3	3	3	3	3	3	26	0.144
f ₁₃	3	2	×	3	4	3	2	2	3	3	25	0.139
f ₁₄	1	0	1	×	3	3	2	2	3	3	18	0.100
f ₂₁	1	1	0	1	×	1	2	2	2	2	12	0.067
f ₂₂	1	1	1	1	3	×	3	2	2	2	16	0.089
f ₂₃	2	2	1	2	2	1	×	2	2	2	16	0.089
f ₂₄	2	2	1	2	2	2	2	×	3	3	19	0.105
f ₃₁	1	1	1	1	2	2	2	1	×	3	14	0.078
f ₃₂	2	1	1	1	2	2	2	1	1	×	13	0.072
total											180	1

After determined the weight coefficient of prefabricated buildings' functional indicators, the experts scoring method (0 to 10) was used to rate the ten functions for five different structural systems of prefabricated buildings including fabricated frame with cast-in-situ shear wall structure, fabricated frame structure, fabricated shear wall structure, double-sided laminated plate shear wall structure, and externally hung and internally cast PCF shear wall structure. In this scoring process, higher score means higher degree of membership, so the final functional coefficient score of each system is obtained.

Model selection steps of prefabricated building structural system

When using value coefficient method to optimize the selection of prefabricated building structural systems, the following assumptions and steps should be performed:

1. If the functional factor coefficient of alternative m is f_{m1}, f_{m2}, ..., f_{mi0} and the score of each function is p_{m1}, p_{m2}, ..., p_{mi0}, then the function coefficient of alternative m is F^m as shown in formula 1

$$F^m = \frac{\sum_{r=1}^{10} p_{mr} f_{mr}}{\sum_{m=1}^n \sum_{r=1}^{10} p_{mr} f_{mr}} \quad \dots \text{Formula 1}$$

2. If the cost of alternative m is C_m, the cost coefficient of alternative m is C_m as shown in formula 2

$$C^m = \frac{C_m}{\sum_{m=1}^n C_m} \quad \dots \text{Formula 2}$$

3. For alternative m with function coefficient of F^m and cost coefficient of C^m, its value coefficient is V^m as shown in formula 3

$$V^m = \frac{F^m}{C^m} \quad \dots \text{Formula 3}$$

4. After ranking the alternatives based on their value coefficient, the one with the highest value coefficient is selected as the optimal alternative. The model implementation process is as shown in Figure 3.




Figure 3: Algorithm flow of type selection of prefabricated building structural system.

Case Study

Information of the project

A planned building with 17 floors and total floor area of 3925m² in an industrial zone in Changsha, China is selected as case study object. It has three alternative systems: traditional cast-in-situ structure, prefabricated frame cast-in-situ shear wall structure and externally hung and internally cast PCF shear wall structural system.



This case study assumes the following research premises:

- a) The traditional cast-in-situ structure, fabricated frame cast-in-situ shear wall structure and “externally hung and internally cast” PCF shear wall structural system are built in the same geographical location.
- b) Eliminate the influence of force majeure factors and artificial demolition and other factors.
- c) According to the design service life of residential buildings, this paper takes the life cycle of the building as 60 years.
- d) Consider inflation and bank interest rate and set the discount coefficient as 10%.

Calculation of alternatives cost coefficient

Basic information of the calculation

- a) The cost of the alternative system (fees, taxes, safe and civilized construction costs, etc.) is mainly based on the consumption standard of Hunan housing construction and decoration projects in 2020 (base price version)
- b) Price of main materials: the prefabricated components are calculated according to the main data provided by Hunan Provincial Housing Construction Standards; The traditional cast-in-place concrete structure is calculated according to the market price of Hunan Province, and the price of other materials is included according to the market price

- c) Labor cost, machinery cost and other related costs shall be included according to the market price of Hunan Province;
- d) The Chinese yuan is used as the unit of currency in this case study.

In summary, the unit prices and costs of the main components of the alternative system are summarized in Table 4 and Table 5

Table 4: Comparison of unit prices of main components of three alternative systems.

Name	Unit	Unit price		
		Traditional cast-in-place structure	External hanging and internal pouring PCF shear wall structure	Fabricated frame cast-in-situ shear wall structure
exterior wall	m ³	646.597	2492.92	2610.62
Interior wall	m ³	646.436	2303	2583.006
column	m ³	628.78	2590.31	2590.31
beam	m ³	642.647	2578.46	2578.46
floor	m ³	646.92	2221.42	2221.42
stairs	m ³	187.107	2433.1	2433.1

Table 5: Summary of costs of three alternative systems.

Name	Total Price			Unit Price (yuan/square meter)		
	Traditional cast-in-place	Externally hung and internally cast PCF shear wall	Fabricated frame cast-in-situ shear wall	Traditional cast-in-place	Externally hung and internally cast PCF shear wall	Fabricated frame cast-in-situ shear wall
Direct costs	3971472.00	4393174.00	4703994.75	1011.84	1119.28	1198.47
depreciation charge		140581.57	150527.83		35.82	38.35
profit		499503.88	534844.20		127.26	136.27
Safe and civilized construction cost	177842.52	79516.45	85142.30	45.23	20.26	21.69
Fees	88087.25	39538.57	42335.95	22.44	10.07	10.79
Taxes	436861.92	483249.14	517439.42	111.30	123.12	131.83
Input tax deduction	-281974.51	-487642.31	-522143.42	-71.84	-124.24	-133.03
Total	4392289.18	5147921.3	5512141.03	1118.97	1311.57	1404.37
difference					192.60	285.40

**Cost coefficient of alternative structural system****a) Production cost C_1** **i. Decision Making Cost (C_{11})**

After consulting researchers in relevant industries, we know that the allocation of decision-making costs in the three alternative systems is the same, which has no impact on the estimation of their full life cycle costs. Therefore, we assume that the cost of this part is P yuan, that is, $C_{11}=P$ yuan.

ii. Design Cost (C_{12})

According to the consultation and data review, the design cost is calculated in yuan/ m^2 , and the prices for the three systems are 15 yuan/ m^2 , 19 yuan/ m^2 and 17 yuan/ m^2 respectively.

Thus, the total design cost for each alternative is as follows:

Traditional cast-in-situ $C_{12}=15 \times 3925=58900$ yuan
Externally hung and internally cast PCF shear wall $C_{12}=19 \times 3925=74600$ yuan
Fabricated frame cast-in-situ shear wall $C_{12}=17 \times 3925=66700$ yuan

iii. Construction and installation cost (C_{13})

After reviewing the industry's standard and market conditions, the construction and installation costs of three alternatives are as follows [35]:

Traditional cast-in-situ $C_{13}=6,856,900$ yuan
Externally hung and internally cast PCF shear wall $C_{13}=8,609,400$ yuan
Fabricated frame cast-in-situ shear wall $C_{13}=8,973,600$ yuan

iv. Facility Cost (C_{14})

Under the same use conditions, the allocation of the facility cost of the building is the same regardless its structural system [36]. Therefore, it is assumed that the cost of this part is Q 10,000yuan, that is, $C_{14}=Q$ 10,000yuan for all three alternatives.

Thus, by take the sum of four costs calculated above, the total production cost for each structural system is:

For the traditional cast-in-situ system, the construction and installation cost is $C=C_{11}+C_{12}+C_{13}+C_{14}=P+5.89+685.69+Q=P+Q+6,915,800$ yuan, its net present value is $NPV_1=P+Q+6,915,800$ yuan.

For the externally hung and internally cast PCF shear wall system, the construction and installation cost is:

$C_1=C_{11}+C_{12}+C_{13}+C_{14}=P+7.46+860.94+Q=P+Q+8,684,000$ yuan, its net present value is $NPV_1=P+Q+8,684,000$ yuan

For the fabricated frame cast-in-situ shear wall system, the construction and installation cost is:

$C_1=C_{11}+C_{12}+C_{13}+C_{14}=P+6.67+897.36+Q=P+Q+9,040,300$ yuan, its net present value is $NPV_1=P+Q+9,040,300$ yuan

b) Use-cost C_2 **i. Property management cost(C_{21})**

In Changsha, the property management cost is priced according to the property management company's qualification level. The higher qualification level charges higher fees, which normally ranges from 0.5 to 4 yuan/month/ m^2 . This paper calculates the general charge of Changsha property as 1.8 yuan/month/square meter. Therefore, the property management cost $C_{21}=1.8 \times 12 \times 3925=84,800$ yuan for all structural systems.

ii. Energy consumption cost(C_{22})

According to the market survey, the building energy consumption cost of the traditional cast-in-place structural system is 23.79 yuan/year/ m^2 . As the prefabricated structural system has better light bearing performance and thermal insulation performance, its energy consumption cost is smaller [37]. The energy consumption cost of the prefabricated structural system building is determined to be 15.89 yuan/year/square meter. So, the energy consumption cost for each structural system is:

Traditional cast-in-place $C_{22}=23.79 \times 3925=93400$ yuan
Externally hung and internally cast PCF shear wall $C_{22}=15.89 \times 3925=62700$ yuan
Fabricated frame cast-in-place shear wall $C_{22}=15.89 \times 3925=62700$ yuan

iii. Repair Cost (C_{23})

In the current industry practices, for traditional cast-in-situ buildings, major repair is needed every 15 years, that is, in its design service life, three major repairs need to be performed and the price for each repair is 150,000, 250,000 and 400,000 yuan. For prefabricated buildings, due to their higher quality, major repairs are only needed every 20 years [38] and the price for each repair is 200,000 and 400,000 yuan.

iv. Maintenance Cost (C_{24})

According to current market specifications in Hunan province, the standard for the maintenance fee of traditional cast-in-place structural buildings is 101 yuan per square meter, and the standard for that of prefabricated buildings is 51.9 yuan per square meter. So, the maintenance fees for each structural system is:

Traditional cast-in-place $C_{24}=101 \times 3,925=396,400$ yuan
Externally hung and internally cast PCF shear wall $C_{24}=51.9 \times 3,925=203,700$ yuan
Fabricated frame cast-in-situ shear wall $C_{24}=51.9 \times 3,925=203,700$ yuan

Therefore,

The net present value of the alternatives' use-costs is:

Traditional cast-in-place structure:

$NPV_2=(8.48+9.34) \times (P/A, 10\%, 60)+15 \times (P/F, 10\%, 15)+25 \times (P/F, 10\%, 30)+40 \times (P/F, 10\%, 45)+39.64 \times (P/F, 10\%, 60)=177.61+3.59+1.43+0.55+0.13=1,833,100$ yuan

Externally hung and internally cast PCF shear wall structure:

$NPV_2=(8.48+6.27) \times (P/A, 10\%, 60)+20 \times (P/F, 10\%, 20)+40 \times (P/F, 10\%, 40)+20.37 \times (P/F, 10\%, 60)=147.02+2.97+0.88+0.07=1,509,400$ yuan

Fabricated frame cast-in-situ shear wall structure:

$NPV_2=(8.48+6.27) \times (P/A, 10\%, 60)+20 \times (P/F, 10\%, 20)+40 \times (P/F, 10\%, 40)+20.37 \times (P/F, 10\%, 60)=147.02+2.97+0.88+0.07=1,509,400$ yuan

c) Demolition and recovery cost C_3

After the service life of the traditional cast-in-place structure is completed, its net residual value accounts for about 3% of the construction and installation cost, while after the service life of the prefabricated structural system is reached, its net residual value accounts for about 10% of the construction and installation cost [39] (Figure 4). So, the demolition and recovery cost and the present net value for each structural system is:

Traditional cast-in-place cost:

$C_3=685.69 \times 3\%=205,707$ yuan

Traditional cast-in-place NPV:

$NPV_3=20.57 \times (P/F, 10\%, 60) = 700$ yuan

Externally hung and internally cast PCF shear wall:

$C_{24}=51.9 \times 3,925=203,700$ yuan

Externally hung and internally cast PCF shear wall NPV:

$NPV_3=86.09 \times (P/F, 10\%, 60) = 2,800$ yuan

Fabricated frame cast-in-situ shear wall:

$C_{24}=51.9 \times 3,925=203,700$ yuan

Fabricated frame cast-in-situ shear wall NPV:

$NPV_3=89.74 \times (P/F, 10\%, 60) = 2,900$ yuan

d) NPV of the Life Cycle Cost of the alternative Structural systems

Traditional cast-in-place:

$NPV=NPV_1+NPV_2-NPV_3=P+Q+691.58+183.31-0.07=P+Q+8,748,200$ yuan

Externally hung and internally cast PCF shear wall:

$NPV=NPV_1+NPV_2-NPV_3=P+Q+868.40+150.94-0.28=P+Q+10,190,600$ yuan

Fabricated frame cast-in-situ shear wall:

$NPV=NPV_1+NPV_2-NPV_3=P+Q+904.03+150.94-0.29=P+Q+10,546,800$ yuan




Figure 4: Life cycle comparison of alternative systems.

Table 7: Scoring alternative architecture

	f11	f12	f13	f14	f21	f22	f23	f24	f31	f32	Weighted Score	Function coefficient
	0.117	0.144	0.139	0.1	0.067	0.089	0.089	0.105	0.078	0.072		
A1	7	6	6	7	6	6	6	6	6	6	6.217	0.27
A2	9	9	8	8	9	9	9	10	9	9	8.866	0.385
A3	8	8	7	7	8	8	9	9	8	8	7.955	0.345
total											23.038	1

Value coefficient of each alternative structural system

After a combined analysis of the life-cycle cost coefficient and functional coefficient of the three alternative structural systems, the value coefficient of each alternative can be calculated and the results are shown in Table 8.

Table 8: Value coefficient analysis of alternative structural system.

Program	Function coefficient	Cost coefficient	Value coefficient
Traditional cast-in-place structure	0.27	0.297	0.909
Externally hung and internally cast PCF shear wall structure	0.385	0.346	1.113
Fabricated frame cast-in-situ shear wall structure	0.345	0.357	0.966

The following conclusions can be drawn from the results:

The life cycle cost of the cast-in-place structural system has the lowest LCC, which seems to be the optimal option, however, its functional coefficient is the lowest among the alternative systems, so its value index is smaller than the other two alternative systems. The prefabricated frame cast-in-situ shear wall structural system has the highest life-cycle cost coefficient, but its functional coefficient is high, so its value coefficient is higher than that of the cast-in-situ structural system.

The functional coefficient of the externally hung and internally cast PCF shear wall structural system is the highest among the alternative systems, and its life-cycle cost coefficient is in the middle, so its value coefficient is highest. The comparative analysis of the three alternative systems shows that the externally hung and internally cast PCF shear wall structural system can achieve the maximum functional value with less cost. Therefore, through the value coefficient analysis, the external hanging and internal pouring PCF shear wall structural system should be selected in this case.

e) Cost Coefficient of the Alternative Structural systems

The cost coefficient of each alternative is as shown in Table 6.

Table 6: Cost coefficient of alternative structural system.

Programme	Traditional cast-in-place structure	Externally hung and internally cast PCF shear wall structure	Fabricated frame cast-in-situ shear wall structure
Cost coefficient	0.297	0.346	0.357

Functional coefficient of each alternative structural system

For the cast-in-place structural system, the externally hung and internally cast PCF shear wall structural system, and the fabricated frame cast-in-place shear wall structural system, the expert scoring method of 10 points system is used to score the functions. As shown in Table 7, A1 refers to cast-in-situ structural system, A2 refers to externally hung and internally cast PCF shear wall structural system, and A3 refers to fabricated frame cast-in-situ shear wall structural system.

Conclusion

This paper mainly analyzed five kinds of concrete prefabricated building structural systems, and established a model for the structural system selection based on value engineering. During the course of completing the research and from the results of the provided case study, the following conclusions are drawn:

- a) Greater development of prefabricated buildings is inevitable, aside from developing new prefabrication techniques, it is also very important to diversify the approach being used to select suitable structural systems. The model proposed in this paper not only provides insight to the factors that can be considered in the structural system selection stage, but also gives attention to solving this problem from a life cycle perspective.
- b) Different prefabricated structural systems along with the traditional cast-in-place structure have significantly different function coefficients and cost coefficients. This further confirms the importance of using value coefficient as an indicator in the structural system selection stage because the preference of each stakeholder of a construction project often varies. For example, the investors always tend to minimize the financial cost while the architecture focuses on the aesthetic perspectives and the structural engineers mainly consider the construction feasibilities.
- c) From the LCC analysis, it can be noticed that prefabricated buildings have higher cost than traditional buildings. This confirms the current market situation of prefabricated buildings and the main reason causing the high cost is that prefabricated buildings are still not fully industrialized, only limited companies and factories are able to provide professional detailed design and prefabricated components production services which makes the unit price of prefabricated buildings are higher than traditional buildings.
- d) From the case study, it is found that the value coefficients of prefabricated building structures are higher than that of the traditional cast-in-place building. This indicates that despite the fact that prefabricated buildings have higher costs, they can achieve higher value through their life cycles, which give more indirect benefits in long term.



Future Works

In the life-cycle cost analysis, various factors can affect the calculation results, and thus affect the decision-making in the structural system selection process. Therefore, if more data is available, the accuracy of the LCC estimations of all building types can be further improved. In addition, in real-world applications, the market factor, policy factor and other external factors that can have influence on the structural system selection results should also be considered.

Funding Information

This study was supported by the Guangzhou City Construction College 2023 School-level Research Projects (2023XKZY02).

Reference

1. Aye L, Ngo T, Crawford RH, Gammampila R, Mendis P (2015) Life cycle greenhouse gas emissions and energy analysis of prefabricated reusable building modules. *Energy and Buildings* 47: 159-168.
2. Jaillon L, Poon CS (2016) Life cycle design and prefabrication in buildings: a review and case studies in Hong Kong. *Automation in Construction* 39: 195-202.
3. Jeong J, Hong T, Ji C, Kim J, Lee M, et al. (2017) An integrated evaluation of productivity between prefabricated and conventional columns. *Journal of Cleaner Production* 142: 2393-240.
4. Hong J, Shen GQ, Mao C, Li Z, Li K (2016) Life-cycle energy analysis of prefabricated building components: an input output-based hybrid model. *Journal of Cleaner Production* 112: 2198-2207.
5. Fragiaco M, Lukaszewska E (2013) Time-dependent behaviour of timber-concrete composite floors with prefabricated concrete slabs. *Engineering Structures* 52: 687-696.
6. Adekunle TO, Nikolopoulou M (2016) Thermal comfort, summertime temperatures and overheating in prefabricated timber housing. *Building and Environment* 103: 21-35.
7. Arashpour M, Wakefield R, Abbasi B, Lee EWM, Minas J, et al. (2016) Off-site construction optimization: Sequencing multiple job classes with time constraints. *Automation in Construction* 71(2): 262-270.
8. Mitterhofer M, Schneider GF, Stratbuecker S, Sedlbauer K (2017) An FMI-enabled methodology for modular building performance simulation based on Semantic Web Technologies. *Building & Environment* 125: 49-59.
9. El Abidi K, Ghazali F (2015) Motivations and Limitations of Prefabricated Building: An Overview. *Applied Mechanics and Materials* 802: 668-675.
10. Zhengdao CL, Hong J, Xue F, Qiping SG, Xu X, et al. (2016) SWOT analysis and Internet of Things-enabled platform for prefabrication housing production in Hong Kong. *Habitat International* 57: 74-87.
11. Xueyan F, Shanglai L (2021) An Economic Benefit Analysis of Prefabricated Buildings. *Architectural Design Management* 38(4): 48-54.
12. Guilin W (2021) An Economic Benefit Analysis of Prefabricated Buildings. *Business News* (25): 150-152.
13. Feng Z, Gang L (2021) Research and application of Prefabricated Building information Management Platform based on BIM and Internet of Things. *Civil Construction Engineering Information Technology* 13(3): 101-106.
14. Zhigang R, Hongqing Z (2019) Research on Assembly Building Information Management Based on BIM. *Shanxi Construction* 45(20): 180-181.
15. Xin LZ, Zhao GY, Chao Z, Song DX, Kun Y (2018) Analysis of seismic performance parameters of frame structure with assembled damping wallboard. *Sichuan Institute of Architectural Sciences* 44(4): 19-24.
16. Kun HX, Yu TC, Lin WM, Ran L (2018) The Research and Practice of Prefabricated Concrete Structure in China. *Building Science* 34(9): 50-55.
17. Cheng CZ (2022) Construction technology of prefabricated concrete construction structure. *Sichuan Building Materials* 48(2): 135-136.
18. Jun LW, Jiang SY, Lei Z (2018) Research and Thinking on Prefabricated Building Structural system Based on New Rural Construction. *Structural Engineer* 34(2): 173-179.
19. Yan PJ, Li W, Hui LY (2018) Application of prefabricated design and construction methods in school apartment buildings. *Construction technology* 47(s1): 1606-1610.
20. Bin G (2018) Structural system and design of prefabricated buildings. *Residential Housing and Real Estate* 19: 161.
21. Xin S (2018) Discussion on the structural system and design of prefabricated buildings. *Residential and Real Estate* 24: 131.
22. Qian Z (2020) Cost analysis of prefabricated buildings based on value engineering concept. *Lanzhou University of Technology*.
23. Wan KT, Zhu H, Yuen TYP, Chen B, Hu C, et al. (2018) Development of low drying shrinkage foamed concrete and hygro-mechanical finite element model for prefabricated building facade applications. *Construction and Building Materials* 165: 939-957.
24. Pei NG, Yang D, Ai QL, Yong LF (2021) Seismic properties of connecting nodes of prefabricated concrete frame structures. *Industrial Buildings* 51(2): 171-185.
25. Qing W, Qiang DZ, Jun WZ, Deng Z, Jie LZ (2019) Assembly integral frame-cast-in-place shear wall structure design points and existing problems. *Engineering construction and Design* 4: 23-24.
26. Wu Dun-jun, Li Ning, Wang Jie et al. High-rise prefabricated assembly integral frame-cast-in-place shear wall structure design. *Building structure*, 2015 (12): 54-57,33.
27. Yan L (2015) Assembly of an integral shear wall system. *Value Engineering* 6: 1105-106.
28. Ze XF, Ning W, Zhan QS, Hong XW, Qiu Y (2020) Application of double-sided overlapping shear wall structure in residential projects. *Construction technology* 49(8): 1-4.
29. Shu QY, Jia Z, Sheng ZJ (2017) Application and Research of PCa Internal Casting and Add-in Technology in Residential Industrial System. *Construction technology* 46(15): 61-65.
30. Li LS (2020) Analysis of life cycle engineering cost of construction project. *Home* 13: 105.
31. Xin XC, Wen ZH (2022) Analysis on investment control of design scheme based on value engineering. *Jiang xi building materials* 2: 222-223.
32. Jie DY (2019) Research on structural selection, manufacturing and installation optimization of PC prefabricated building based on value engineering theory. *East China Jiaotong University*.
33. Jie C (2017) Value Engineering Function of Complex Systems-Cost analysis. *Value Engineering* 36(3): 20-23.
34. Ran Z, Zhou L (2017) The Application of Value Engineering in Residential Project Investment Decision Making. *Contemporary Economy* 5: 148-149.
35. Wei DJ (2019) Study on life cycle cost-benefit analysis of prefabricated buildings. *Beijing Jiaotong University*.
36. Xiang DZ (2015) Research on safety risk assessment and control technology in the whole process of construction industrialization. *Xian University of architecture and technology*.
37. Bao KQ, Ya Z, Bo M, Shuai L (2016) Research on comprehensive benefit analysis method of prefabricated building. *Construction technology* 45(4): 39-43.
38. Xia HF (2017) Research on the development and comprehensive benefit analysis of prefabricated buildings. *Theoretical research on urban construction (electronic version)* 26: 3.
39. Shu X (2010) Real estate appraisal. Beijing: Higher Education Press.